

Saving Energy with Ammonia Control at Wastewater Treatment Plants

PRESENTATION ABSTRACT

Author: Dr. Tao Su
Ph.D. Environmental Studies
Process & Treatment, Asia Pacific Product Manager
Xylem (Analytics)

INTRODUCTION

Wastewater Treatment Plants (WWTPs) play a key role in protecting natural water bodies, however they are also one of the largest energy consumers in most countries. In Japan for example, WWTPs consume 0.7% of the country's total electricity [1], and even worse in the European Union at 0.8% [2] and in the USA at 4% [3][4].

Reviewing an entire wastewater treatment plant energy demand (Figure 1), the major usage is wastewater treatment in reaction tanks, contributing to 54% of total energy consumed in Japanese WWTPs [5] and nearly 50% greater than most other countries [4]. Therefore, reducing energy consumption in reaction tanks is the key factor for WWTPs energy-savings.




Figure 1. The breakdown of energy consumed at WWTPs in Japan [6].

To reduce energy consumption, several energy saving methods have been investigated, such as utilizing higher capacity air blowers & efficient diffusers, installing advanced energy-saving reaction mixers and improving sensor feedback control systems [7].

However, considering the balance of capital costs and energy efficiencies, improving sensor control systems is often preferred.

SENSOR CONTROL STRATEGY

Aeration control by Dissolved Oxygen (DO) sensors have been widely applied in WWTPs, dominating sensor control systems. Although recently, a new sensor-based system utilizing ammonia sensors has been widely and deeply investigated by the Japanese Government [8].

In order to focus on the dominant sensor-based control systems, this paper will review the following:

- Dissolved Oxygen (DO) sensor aeration control
- Ammonia sensor-based aeration control, including in combination with DO sensors.

Figure 2 is a simplified illustration of the dominant sensor control systems. The important features of process control are on-off control, set-point control and feedback/ feedforward control. These are applied to achieve an optimized result. The focus of this paper is to study the sensors.




Figure 2. Comparing DO sensor aeration and Ammonia sensor control systems.

ENERGY-SAVING PRINCIPLES

Ideally, there is no wasted energy if oxygen demand within an Aeration tank is just satisfied via aeration from air blowers. But in reality, excess aeration is supplied because DO is used as a parameter to evaluate oxygen demand within a DO sensor-based control system (e.g. DO set-point control).

Alternatively, if ammonia is used as the parameter to evaluate oxygen demand then we are given a much more sensitive and accurate reflection of the real oxygen demand in an aeration tank. The use of an ammonia sensor to control air blowers (ammonia control system) results in the avoidance of excessive aeration.

Figure 3 illustrates the basic mechanism for energy-savings in WWTPs. During low organic loading periods, oxygen demand is correspondingly low, when an ammonia sensor is installed this can stop excess aeration. While during high organic loading periods, an installed ammonia sensor transmits the correct oxygen demand to the controller and ensures appropriate aeration is provided. Under both conditions installing, ammonia sensors will result in good water treatment quality.




Figure 3. Air supplied with DO and Ammonia sensor control systems.

APPLICATION EXAMPLES

Ammonia sensor control systems use as an energy-saving strategy whereby Nitrogen is removed. This has been recognized for many years [9], though currently it has been demonstrated as a very efficient approach in all biological wastewater treatment processes. In Japan, significant progress has been achieved by utilizing ammonia sensor feedback control systems.

In addition to saving 10%~20% energy, treated water quality meets government discharge regulations (Table 1) [10].

Table 1, Energy-saving field test in Japan [10]

Test No.*	Treatment Process	Energy Reduced
Case 1	Standard activated sludge process	14.8%
Case 2	Standard activated sludge process	16.9%
Case 4	Denitrification/Nitrification	23%
Case 5	Denitrification/Nitrification	40%
Case 6	Standard activated sludge process	10%
Case 8	Standard activated sludge process	19%

*Case 3, 7 and 9 are not referred because energy-saving is not achieved by utilizing ammonia sensor control system

In addition to the field tests reported by reference 6, there are significant numbers of published research papers summarized in Table 2. Energy savings as high as 25% have been achieved in various treatment processes: standard activated sludge (AS) process, Anoxic-Oxic process (AO, Nitrogen removal) and Anaerobic-Anoxic-Oxic process (A2O, Nitrogen & Phosphorus removal).

Table 2, Energy-saving by ammonia sensor research reported.

Treatment Process	WWTP Capacity	Energy Reduced	Ref.
Anaerobic -Anoxic-Oxic	40,000 m ³ /d	16%	[11]
Anoxic -Oxic	200,000 m ³ /d	10.4%	[12]
Standard AS process	68,700 m ³ /d	8.7%	[13]
Anoxic- Oxic	Not showed	2.3~8.9%	[14]
Anoxic- Oxic	107,000 m ³ /d	16.9%	[15]
Standard AS process	44,000 m ³ /d	10~15%	[16]
Anoxic- Oxic	7,200 m ³ /d	9.9~17.2%	[17]
Anaerobic-Anoxic- Oxic	830,000 m ³ /d	10~25%	[18]
Anaerobic-Anoxic- Oxic	700,000 p. e.	18%	[19]



a xylem brand

WTW AMMONIA SENSOR

WTW (a Xylem brand) AmmoLyt® Plus 700 series Ammonia Sensor (Figure 4) has been utilized globally, including installations in Japan [21], [22]. More than 20,000 (NH₄&NO₃ sensor included) units have been sold world wide. Noteworthy is that the AmmoLyt® Plus has been adopted by the Tokyo Bureau of Sewerage of the Tokyo Metropolitan Government in Shibaura WWTP and has achieved a more than 20% electricity energy reduction [18].



Figure 4. WTW ammonia sensor : AmmoLyt® Plus 700

Features of AmmoLyt® Plus 700 series

- High Accuracy with K+ Dynamic compensation
- Economical by stability over long periods of time
- User friendly with electrode, simply cable exchange
- Maintenance simplified with compress air auto-cleaning.

SUMMARY

Compared with conventional dissolved oxygen sensor aeration control systems, the ammonia sensor control system saves significantly more energy in various treatment processes. [Contact Xylem for more information.](#)

REFERENCES

- [1] 西田佳記, “環境負荷低減に向けた下水処理プロセスおよび制御技術に関する研究,” 1392.
- [2] D. Ganora et al., “Opportunities to improve energy use in urban wastewater treatment: A European-scale analysis,” *Environ. Res. Lett.*, vol. 14, no. 4, 2019.
- [3] Electric Power Research Institute, “Water and Sustainability: U.S. Electricity Consumption for Water Supply and Treatment - The Next Half Century,” vol. 4, no. Volume 4, 2000.
- [4] D. Ghernaout, Y. Alshammari, and A. Alghamdi, “Improving energetically operational procedures in wastewater treatment plants,” *Int. J. Adv. Appl. Sci.*, vol. 5, no. 9, pp. 64–72, 2018.
- [5] 公益財団法人 日本下水道新技術機構, “オキシレーションディッチ法の省エネ技術に関する共同研究,” 2017.
- [6] 国土交通省, “下水道における 資源・エネルギー施策の現状分析,” <https://www.mlit.go.jp/>, 2013. .
- [7] 下水道部国土交通省 水管理・国土保全局, “下水処理場のエネルギー最適化に向けた 省エネ技術導入マニュアル (案),” 2019.
- [8] “B-DASH プロジェクト No.14 ICTを活用した効率的な硝化運転制御技術導入ガイドライ(案),” 国土技術政策総合研究所資料, vol. 938, 2016.
- [9] N. Leiprecht, “Optimization of wastewater treatment plants,” in セントラル科学株式会社「水処理・測定技術セミナー」.
- [10] “センサー等を活用した段階的高度処理に関する調査研究 政策支援調査研究,” 下水道新技術研究所年報 [要約版], p. 6597, 2017.
- [11] 小原卓巳、足利伸行、山中理、山本勝也, “下水処理におけるシミュレーション技術の活用,” pp. 42–46.
- [12] 遠藤和広、田崎敏郎, “アンモニア計とDO計を用いた送風量制御システムの開発,” 第47回下水道研究発表会講演集, pp. 918–920, 2010.
- [13] 榎木辰彦、平岡由紀夫、安部裕宣, “下水処理施設における資源の有効活用と省エネ・省コスト運用に貢献する技術.pdf,” 東芝レビュー, vol. 69, no. 5, pp. 20–23, 2014.
- [14] 山中理、海老原聡美、難波諒, “環境負荷低減と省エネや省コストを実現する上下水道施設のプラント運用技術,” 東芝レビュー, pp. 28–32, 2015.
- [15] 道中敦子西田佳記、山野井一郎、武本剛、中村信幸、片倉洋一、辻井優樹, “アンモニアセンサを活用した硝化制御システム 西,” 環境システム計測制御学会, vol. 21, pp. 23–26, 2016.
- [16] 長塩尚之、田端隆雄、宇代晋也、竹原輝巳, “下水処理施設に於けるアンモニア態窒素濃度計の活用検討,” 日新電機技報, vol. 62, no. 3, pp. 70–75, 2017.
- [17] 島田光重、熊田浩英、石山明, “省エネ機器とアンモニア制御による低動力反応タンクシステムの性能実証,” 神鋼環境ソリューション技報, vol. 15, no. 1, 2018.
- [18] 葛西孝司、曾根啓一、鈴木重浩, “好気タンク内の脱窒を利用した新たな高度処理技術(同時硝化脱窒処理)の開発,” 下水道協会誌, vol. 52, no. 635, pp. 114–122, 2015.
- [19] A. Thunberg, A. Sundin, and B. Carlsson, “Energy optimization of the aeration process at Käppala wastewater treatment plant,” 10th IWA Conf. Instrumentation, Control Autom., 2009.
- [20] L. Rieger, I. Takács, and H. Siegrist, “Improving Nutrient Removal While Reducing Energy Use at Three Swiss WWTPs Using Advanced Control,” *Water Environ. Res.*, vol. 84, no. 2, pp. 170–188, 2012.
- [21] 湛記先、池畑将樹、小泉栄一、池田洋平, “自動洗浄機能を備えた水質測定ユニットの開発と下水処理場での活用 湛,” 環境システム計測制御学会, vol. 19, pp. 129–132, 2014.
- [22] 湛記先、小泉栄一、黛将志、川口幸男、橋本敏一, “流入水質のオンライン測定と酸素必要量 (OR) 計算に基づいた実下水処理場の曝気制御,” 環境システム計測制御学会, vol. 17, pp. 47–50, 2012.